# **PCT**

# WORLD INTELLECTUAL PROPERTY ORGANIZATION International Bureau



## INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 6:

(11) International Publication Number:

WO 98/36612

H04Q 11/04

**A2** 

(43) International Publication Date:

20 August 1998 (20.08.98)

(21) International Application Number:

PCT/FI98/00125

(22) International Filing Date:

11 February 1998 (11.02.98)

(30) Priority Data:

970602

12 February 1997 (12.02.97) FI

(71) Applicant (for all designated States except US): NOKIA TELECOMMUNICATIONS OY [FI/FI]; Keilalahdentie 4, FIN-02150 Espoo (FI).

(72) Inventors; and


- (75) Inventors/Applicants (for US only): VIALÉN, Jukka [FI/FI]; Tyrskykuja 3 B 13, FIN-02320 Espoo (FI). MÄENPÄÄ, Sanna [FI/FI]; Hauenkalliontie 8 D 9, FIN-02170 Espoo (FI).
- (74) Agent: KOLSTER OY AB; Iso Roobertinkatu 23, P.O. Box 148, FIN-00121 Helsinki (FI).

(81) Designated States: AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CU, CZ, DE, DK, EE, ES, FI, GB, GE, GH, GM, GW, HU, ID, IL, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, UA, UG, US, UZ, VN, YU, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, ML, MR, NE, SN, TD, TG).

#### **Published**

In English translation (filed in Finnish). Without international search report and to be republished upon receipt of that report.

(54) Title: MOBILITY AND CALL CONTROL IN AN ATM ENVIRONMENT



#### (57) Abstract

The invention relates to ATM (Asynchronous Transfer Mode) systems, and particularly to mobility and call control management therein. A wireless ATM network comprises at least one ATM switch (30), and base stations (BTS) connected to the ATM switch by a user-network-interface (UNI) interface. In addition, at least one controlling network element of a conventional PLMN network, such as a mobile telephone exchange (MSC) or a base station controller (BSC), which is responsible for the mobility management and call control, is connected to the ATM network by the UNI interface. A permanent virtual channel is provided between the base station and the controlling PLM element for PLM-specific signalling (signalling related to, for example, call control, mobility management or radio resource management). The ATM switch (30) therebetween forwards the signalling without interpreting it in any way. The PLMN element (MSC, BSC) remotely controls the ATM switch to switch a virtual connection between the base station (BTS) and another point according to the ATM standards.

ing pagamanan kan menganan di sebagai kenangan di sebagai kenangan di sebagai kenangan di sebagai kenangan di Banggan manangan sebagai kenangan di sebagai kenangan di sebagai kenangan di sebagai kenangan di sebagai kenan

and the second s

## FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

L	Albania	ES	Spain	ĻS	Lesotho	SI	Slovenia
M	Amenia	FI	Finland	LT	Lithuania	SK	Slovakia
T	Austria .	FR	France	LU	Luxembourg	SN	Senegal
U	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
Z	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad,
3A	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
ΒE	Belgium	GN	Guinea	MK	The former Yugoslav	TM	Turkmenistan
3F	Burkina Faso	GR	Greece		Republic of Macedonia	TR	Turkey
3G	Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
ij	Benin	IE	Treland	MN	Mongolia	UA	Ukraine
R	Brazil	IL	Israel	MR	· Mauritania	UG	Uganda '
Y	Belarus	IS	Iceland	MW	Malawi	US	United States of America
A	Canada	IT	Italy	MX	Mexico	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NE	Niger	VN	Viet Nam
CG	Congo	KE	Kenya	NL	Netherlands	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NO	Norway	zw	Zimbabwc
CI.	Côte d'Ivoire	KP	Democratic People's	NZ	New Zealand		
CM	Cameroon		Republic of Korea	PL	Poland		
CN	China	KR	Republic of Korea	· PT	Portugal		
Ü	Cuba	ΚZ	Kazakstan	RO	Romania		1.00
z	Czech Republic	LC	Saint Lucia	RU	Russian Federation		
E	Germany	LI	Liechtenstein	SD	Sudan		
K	Denmark	LK	Sri Lanka	SE	Sweden		
EE	Estonia	LR	Liberia	SG	Singapore		

WO 98/36612 . PCT/FI98/00125

#### MOBILITY AND CALL CONTROL IN AN ATM ENVIRONMENT

#### FIELD OF THE INVENTION

The invention relates to ATM (Asynchronous Transfer Mode) systems and particularly to mobility and call control management therein.

### 5 BACKGROUND OF THE INVENTION

Current telecommunication comprises two trends of particular interest: mobile communication and broadband networks. The term broadband typically refers to a bit rate higher than 2 Mbit/s. The term narrowband usually refers to a bit rate of 64 kbit/s or lower. The term wideband occasionally refers to bit rates from 64 kbit/s to 2 Mbit/s. There are at least two (compatible) reasons for the interest in the broadband networks:

- 1) One broadband bearer shared among several users, few or none of whom need the whole bandwidth alone, can offer advantages concerning the establishment and flexibility of transmission systems.
- 2) Information to be transmitted over separate transmission channels may demand broadband channels. Users need new high-quality services which, in turn, call for high bit rates. Such services include for example video conferencing, high-speed data transmission etc. A common denominator for these services is multimedia where image, voice and data are integrated into one service.

Owing to its many strengths, ATM (Asynchronous Transfer Mode) is chosen as the data transmission technique in several protocol structures standardized for a B-ISDN (Broadband Integrated Services Digital Network). In this context, the term transmission refers to the use of ATM switching and multiplexing techniques at a data link layer (i.e. an OSI Layer 2, hereinafter referred to as an ATM layer) for transporting end-user traffic from a source to a destination within the network. Virtual connections are set up between the source and the destination, which requires that the network must be provided with switching operations. Signalling and user information are normally transported on different virtual connections at the ATM layer. A virtual connection is identified at the ATM layer by means of a virtual path identifier (VPI) and a virtual channel identifier (VCI).

In ATM, information is transported split in fixed-length cells, whereby the number of the cells in a time unit is proportional to the user's

bandwidth requirements. Each 53-octet cell is divided into a 5-octet header and a 48-octet information field as shown in Figure 2.

The primary purpose of the header is to identify a connection number for a cell sequence that sets up a virtual channel for a particular call. Several virtual paths that are multiplexed in the ATM layer can be connected to the same physical layer (i.e. an OSI Layer 1), whereby each path is identified by an 8-bit VPI at a user-network-interface (UNI) and by a 12-bit VPI at a network node interface. Each path can comprise several virtual channels, each of which is identified by a 16-bit VCI. The header can also comprise other fields, such as a header error control (HEC), a generic flow control (GFC), a cell loss priority (CLP) and a payload type (PT).

The user-network-interface UNI between an ATM terminal and an ATM switch (a private UNI) and between private and public ATM networks (a public UNI) together with an associated UNI signalling (and an ATM cell) are specified at least in the following specifications:

[1] ATM User-Network-Interface Specification, version 3.1, ATM Forum, 1994

[2] ATM User-Network-Interface (UNI) Signalling Specification, version 4.0, ATM Forum, July 1996

[3] ITU-T Recommendation Q.2931 (1994) Broadband Integrated services Digital Network (B-ISDN), Digital Signalling System No. 2 (DSS 2), User-Network Interface (UNI) Layer 3 specification for Basic Call/Connection Control. ITU-T.

In mobile networks (PLMN), radio interfaces have conventionally been narrowband interfaces. Transmission systems in the mobile networks have conventionally been implemented by circuit switched connections in a star or tree network configuration. In order to increase the capacity and flexibility of transmission systems, different broadband packet switched transmission systems, such as WO 9400959 and EP 0366342 have also been proposed for mobile networks. EP0426269 introduces a mobile system wherein base stations are connected to ATM network switches by routers. Virtual connections controlled by the base stations are set up between the base stations through the ATM network. Elementary mobility management is based on routing tables maintained in the base stations and in the ATM switches and updated as the subscribers move in the network.

Another potential future trend is that mobile systems have a broadband radio interface The transmission system of the mobile system should in that case also be a broadband transmission system, a potential alternative thereof being the ATM technique.

A third trend is to introduce wireless data transmission (wireless ATM) and mobility into ATM networks (wireless ATM). However, the problem with this trend is that current B-ISDN and ATM standards in no way support the mobility management, subscriber authentication, call control, etc., required by wireless communication. Introducing these additional features required by 10 wireless communication into the ATM network calls for considerable development and standardization work to be carried out and significant modifications to be made to the existing ATM systems. Implementing wireless ATM is therefore a slow and an expensive process. Such a process conducted by wireless ATM work groups is about to start in the ATM Forum:

# 15 BRIEF DESCRIPTION OF THE INVENTION

An object of the invention is to enable the introduction of wireless data transmission and mobility into an ATM network without significant modifications to the existing ATM networks and standards.

The invention relates to a wireless ATM network comprising mobile stations, base stations and at least one ATM switch, the base stations being connected to the ATM switch by a user-network-interface (UNI). The invention is characterized in that at least one controlling PLMN network element is connected to said ATM switch by the UNI interface to carry out call control and mobility management,

a first permanent ATM virtual channel is provided between said PLMN network element and each base station for transferring call control and mobility management signalling transparently therebetween through the ATM network.

said PLMN network element is arranged to remotely control said 30 ATM switch to switch ATM virtual channels dynamically between the base stations and another point in the ATM network.

The invention also relates to a cellular radio network as claimed in claim 2 comprising mobile stations, base stations, at least one controlling PLMN network element that is responsible for call control and mobility man-35 agement, and an ATM transmission network comprising at least one ATM

5

20

switch, the base stations and said controlling PLMN network element being connected to the ATM switch by a user-network-interface (UNI).

The invention also relates to methods for mobility management and call control in a wireless ATM network and in a cellular radio network as claimed in claims 9 and 10.

The invention also relates to an ATM switch element as claimed in claim 12 and to a mobile network element as claimed in claim 18.

According to the invention, wireless base stations are connected to an ATM switch by a UNI interface in an ATM network. At least one controlling network element of a conventional PLMN network, such as a mobile telephone exchange and/or a base station controller is also connected to the ATM network by the UNI interface, the controlling network element being responsible for mobility management and call control. There is a permanent virtual channel (PVC) via said ATM switch between the base station and said at least one 15 controlling cellular network element. Signalling related for example to call control, mobility management and/or radio resource management between a mobile station and the controlling cellular network element is transmitted over the permanent virtual channel. The intermediate ATM switch (ATM switches) forwards the signalling without interpreting it in any way. For the ATM switch, the 20 controlling cellular network element and the base station represent an ATM terminal that can be reached via the UNI interface. Furthermore, there is a permanent virtual channel PVC between said at least one cellular network element and said ATM switch. Said controlling network element uses the second permanent virtual channel for commanding from a remote location the 25 ATM switch to switch a virtual connection between the base station and another point according to the ATM standards. According to the invention, all special network elements and special functions related to wireless communication can be implemented by using the network elements and solutions previously designed for the PLMN networks. Designing special solutions for the 30 wireless ATM is thus avoided. These cellular network elements are connected to the ATM network via a standard UNI interface, but the signalling between the cellular network elements takes place transparently through the ATM network via said permanent virtual connections. Thus, the signalling related to wireless communication does not cause modifications to a standard ATM UNI protocol. The only addition required to the ATM switch is functionality by means of which the controlling cellular network element can manipulate the

10

ATM switch operation via the second permanent virtual connection to switch or release the desired virtual connection.

In a preferred embodiment of the invention, an ILMI (Interim Local Management Interface) is used as the signalling interface between the ATM 5 switch and the controlling cellular network element via the permanent virtual connection of the invention. In the preferred embodiment of the invention, remote controlling the ATM switch from the cellular network element is carried out by using an SNMP (Simple Network Management Protocol). The SNMP protocol already includes features which can be applied to control the switching in the wireless ATM network of the invention. The controlling cellular network element then acts as an SNMP manager, and an ATM node contains an SNMP agent. Remote commands are carried in SNMP protocol data units a earlain in eil o fear fear fearte, beinn an Albair

Alternatively, remote controlling according to the invention may be 15 implemented by using UNI signalling without a permanent logical channel between the PLMN network element and the ATM switch. This, however, requires the current UNI signal to be modified in order to enable the switching to be remotely controlled.

In the following, the invention is described in more detail with refer-20 ence to the accompanying drawings, in which

Figure 1 shows a basic architecture for a telecommunication system to which the present invention can be applied,

Figure 2 shows the structure of an ATM cell,

Figure 3 shows the functional architecture of the ATM switch of the 25 invention in a telecommunication system presented in Figure 1,

Figure 4 is a signalling diagram illustrating the data call set-up of the invention,

Figure 5 is a signalling diagram illustrating internal signalling of an ATM switch during the call set-up presented in Figure 4,

Figure 6 is a signalling diagram illustrating the speech call set-up of the invention, .

Figure 7 is a signalling diagram illustrating the handover of the invention between two base stations connected to the same ATM switch.

### DETAILED DESCRIPTION OF THE INVENTION

The present invention can be applied to any broadband network using an ATM technique, for introducing wireless communication and mobility

30

management into the networks. Correspondingly, the invention can be applied to any mobile network for implementing a transmission system between the network elements by means of an ATM network. The final network architecture, signalling and call set-up of the invention is very much alike in both cases.

A mobile system used as a whole, or the network elements thereof being used, for the implementation of a wireless ATM, can be any cellular radio system or some other radio system. In this patent application, a mobile system or a PLMN is taken to mean all the radio systems supporting mobility management.

Different cellular systems may differ from one another as concerns the number and the functions of different types of network elements. Cellular systems may comprise for example only mobile telephone exchanges and base stations or, in addition, also base station controllers. Signalling may also differ greatly between different cellular systems. Such differences are, however, irrelevant to the invention, as system-specific signalling is performed transparently through the ATM network via permanent virtual connections set up between the network elements in accordance with the invention. The control of the ATM switching according to the invention takes place via the permanent virtual connection at the same call set-up stage and by the same network element as specified in the system concerned.

The type of radio interface between the base stations and the mobile stations is also irrelevant to the invention. The radio interface may be a narrowband or a broadband interface, TDMA or CDMA, a satellite, an interface according to a current standard (for example the GSM) or an interface according to a future standard (for example the UMTS).

The European digital cellular mobile communication system GSM (Global System for Mobile Communication) is used as an example in the following description of the preferred embodiments of the invention. The basic components of the GSM system are specified in the GSM specifications. As concerns the most significant description of the GSM system, reference is made to the GSM specifications and "GSM System for Mobile Communications", M. Mouly and M. Pautet, Palaiseau, France, 1992, ISBN:2-9507 190-07-7.

Figure 1 shows a telecommunication system comprising mobile stations MS, base stations BTS, a base station controller BSC, a mobile tele-

7

phone exchange MSC and an ATM network 3 including one or more ATM switches 30. A mobile network PLMN also comprises other network elements. such as subscriber data bases HLR (a home location register) and VLR (a visitor location register) and an operation and maintenance centre (OMC). The home location register HLR permanently contains subscriber information and information indicating the visitor location register VLR in the area of which the mobile station is located at a particular time. The subscriber information regarding subscribers visiting the VLR area is temporarily copied to the visitor location register VLR.

According to the invention, all mobile network operations, such as call control, mobility management and radio resource management are implemented in the PLMN network elements BTS, BSC and MSC. As is usual in the GSM system, the MSC is responsible for call set-up; call switching and call control. A base station system is composed of the base station controller BSC 15 and the base stations BTS. The base station controller BSC is used for controlling several base stations. The BSC can also control a handover between two BTSs connected thereto. An A interface towards the MSC and an Abis interface towards the BTS have been defined for the BSC. These interfaces are specified in the GSM standards. The base stations BTS provide a radio interface through which the mobile stations MS are connected to the BSC and the MSC. 1. 数据的 1. 数数数 4. 二级 and the second of the second of the second of

4

. .

.5

: 4

345

4

The ATM network 3 provides a transmission system that connects the BTS to the other PLMN network elements. The ATM network 3 may also be connected to other ATM networks 2, such as a B-ISDN, or to other data 25 networks 4, such as an N-ISDN, a PSDN (for example X.25) or the Internet. The ATM network 3 is a network preferably offering standard ATM-UNI interfaces whereto permanent virtual connections in accordance with the invention have been set up for PLMN signalling and wherein at least one ATM switch 30 is provided with functionality enabling the PLMN network element to control 30 the switching of the virtual connections via the ATM switch 30.

Figure 3 gives a more detailed description of the telecommunication system signalling architecture shown in Figure 1. For the sake of clarity, only one BTS, one ATM switch 300, one BSC and one MSC are shown in Figure 3. All the interfaces between the ATM switch 30 and the PLMN network elements 35 BTS, BSC and MSC are user-network-interfaces (UNI) drawn by a thick solid line in Figure 3. The UNI interface is specified in references [1], [2] and [3].

5

10

Thus, for the ATM switch, the PLMN network elements represent conventional ATM devices (users) that can be reached over the UNI interface. The PLMN network elements are provided with an ATM adapter that creates a UNI interface towards the ATM network 3 and a PLMN interface towards the network 5 element.

When a telecommunication system presented in Figure 3 is being built, the following permanent virtual connections (PVC) over the UNI interfaces must be set up for the invention:

- 1) PVC1 between the BTS and the MSC (via the switching field 301 of the ATM switch 30). The PVC1 is used to transmit PLMN signalling messages (for example call control, mobility management, authentication, etc.) between the MSC and the MS in the ATM cell payload field.
- PVC2 between the BTS and the BSC (via the ATM switch 30).
   The PVC2 is used to transmit PLMN signalling messages (for example radio
   resource management) between the BSC and the BTS in the ATM cell payload field.
  - 3) PVC3 between the BSC and the MSC (through the ATM switch 30), the PVC3 also being set up for the PLMN signalling (in the ATM cell payload field).
- 4) PVC4 between the MSC and the switching control of the ATM switch 30. PVC5 between the BSC and the switching control of the ATM switch 30. The MSC and the BSC use the PVC4 and the PVC5 to remote control the switching operation of the ATM switch 30 in accordance with the invention.
- It is important to note that the permanent virtual connections PVC can be set up in many alternative ways without deviating from the inventive idea of the invention. For example, the PVC1 may be replaced by a solution wherein the signalling between the MS and the MSC is performed via the BSC by using the PVC2 and the PVC3, the solution hierarchially resembling a conventional GSM network configuration. On the other hand, if the PLMN network does not comprise any base station controller, the permanent virtual channels PVC2, PVC3 and PVC5 then do not exist.

As will be illustrated below by way of examples, all PLMN signalling via the permanent virtual connections PVC1, PVC2 and PVC3 in a preferred embodiment of the invention is substantially in accordance with the GSM specifications. The intermediate ATM network 3 is transparent as regards the

PLMN signalling. All PLMN signalling is transferred in the payload field in the ATM cells that are relayed by the ATM switch 30 without interpreting their contents. Thus, the PLMN signalling messages do not call for any modifications to the ATM UNI signalling protocol.

In a preferred embodiment of the invention, the Interim Local Management Interface (ILMI) specified in references [1] and [2] is used as a remote control interface on the permanent connections PVC4 and PVC5. The ILMI uses an SNMP protocol (Simple Network Management Protocol) for monitoring and controlling management information regarding ATM layer parameters and physical layer parameters over the UNI between the ATM switches and ATM terminals. The SNMP is specified in RFC 1157, A Simple Network Protocol, May 1990. References [1] and [2] also describe the SNMP protocol and messages. The ATM switch includes an agent application supporting the SNMP/ILMI operations. UNI management information is presented in a management information base (MIB) located in the ATM switch. The MIB includes for example the following accessible management information types: a physical layer: an ATM layer; ATM layer statistics; virtual path connections (VPC); virtual channel connections (VCC); and address registration information.

To implement the above described features, the following functional elements are presented in the ATM switch 30 in Figure 3: an SNMP AGENT, a management information base (MIB), an ATM signalling control SIGN.CTRL, a switching matrix 301 and an operation and management interface O&M towards the switching matrix. The ATM signalling control is responsible for the UNI signalling according to references [1] and [2] and controls the switching 25 operations of the switching matrix 301 via the O&M interface. The MIB is the above mentioned data base maintaining status and configuration information on virtual path and virtual channel connections that are available at the UNI interfaces of the ATM switch.

In accordance with the invention, a controlling PLMN element, such as the MSC or the BSC, manipulates the management information by means of the SNMP protocol operations specified in RFC 1157. In the following, Figures 4, 5, 6 and 7 present various examples of the call set-up signalling of the invention. Signalling procedures in the examples are based on the GSM signalling messages.

ting the second of the second

The Control of the Control

5

10

15

20

30

A signalling diagram presented in Figure 4 illustrates a data call set-up originating from an MS. GSM signalling comprises for example a signalling channel request and a grant, CM service requests, authentication, cipher mode setting, and temporary mobile station identifier (TMSI) allocation. The MS sends a SETUP message to a BTS, the message being forwarded to an MSC via a PVC1. The MSC intrepets the address of the receiver of the SETUP message to be an ATM address whose switching can be accomplished via an ATM switch whereto the BTS is connected. If the call set-up is accepted, the MSC sends a CALL PROCEEDING message to the MS via the 10 connection PVC1 and the base station BTS. This message informs the MS that the MSC is handling the call. So far, the description has dealt with normal GSM signalling except that the signalling is transmitted through an ATM network via the permanent virtual connections PVC1, PVC2 and PVC3 of the invention in an ATM cell payload field. Otherwise, this signalling example is irrelevant to the invention and does not need to be described in more detail in this context.

The following example illustrates how the MSC controls an ATM switch 30 to switch a virtual connection (a data connection) between the BTS and a called ATM subscriber before performing the switching of a radio channel. This signalling is presented in block 40 marked off by a dashed line in Figure 4. Signalling in block 40 is also described in Figure 5 that also shows messages between the elements within the ATM switch 30.

With reference to Figures 4 and 5, the MSC sends an SNMP protocol Set-Request-PDU message to the SNMP agent of the ATM switch 30 via a permanent virtual connection PVC4. In this message, the MSC gives an address addr\_1 (the calling party, the BTS) and an address addr\_2 (the called party, the "atm terminal" shown in Figure 4) as parameters, i.e. the address between which a virtual connection should be set up by the ATM switch 30. Both ATM and E.164 addresses may be used.

Next, the SNMP agent uses normal ATM-UNI signalling in order to set-up the connection.

With reference to Figure 5, the SNMP agent sends a connect command to a signalling control unit. The connect command includes as parameters the address addr\_1 and the address addr\_2. A signalling control unit SIGN-CTRL then inquires from an MIB data base by a get\_info command those (ATM switch) ports whereto the addresses addr\_1 and addr\_2 are con-

nected. In its info response, the MIB gives the port numbers and VPI/VCI values to be used for the connections. The signalling control SIGN CTRL then performs a normal ATM connection set-up procedure. First, the SIGN-CTRL sends an ATM\_UNI\_SETUP message to a BTS and an ATM\_NNI\_SETUP message to an ATM switch 40 of the calling party. An ATM switch 41 sends an ATM\_UNI\_SETUP message to a called party (an ATM terminal). The SETUP messages ask different parties to begin with the call set-up. The BTS accepts the call by sending an ATM\_UNI\_CONNECT message to an ATM switch 30. Correspondingly, the called party accepts the call by sending an ATM\_UNI\_CONNECT message to the ATM switch 41. Further, the ATM switch 41 accepts the call by sending an ATM\_NNI\_CONNECT message to the ATM switch 30.

After the successful call set-up described above, the signalling unit SIGN-CTRL commands a switching matrix 301 to actually connect the VPI/VCI of the calling party (BTS) to the VPI/VCI of the called party (the ATM terminal) via an O&M interface (a switch command). The signalling unit SIGN CTRL sends a connect\_ok response to the SNMP agent, the response containing the addresses received in the connect command, the VPI/VCI values being added on these addresses. The SNMP agent then sends an SNMP\_GET\_RESPONSE message to the MSC via the connection PVC4, the message containing said VPI/VCI values.

Next, the MSC sends an ASSIGNMENT REQUEST message to a BSC, the message containing said VPI/VCI values. These values can be either coded into the optional fields of the ASSIGNMENT REQUEST message according to the standard, or new information elements must be added to the message. The BSC performs the required radio resource reservations for said connection and asks the BTS to activate a radio channel by a CHANNEL\_ACTIVATION message. This message must also transmit the VPI/VCI values, i.e. the values must be either coded into the optional fields of the message, or new information elements must be added to the message. The BTS can switch the radio channel for the ATM connection by using the aforementioned information. The signalling then follows normal GSM call set-up signalling except that the MSC sends a CONNECT message to the mobile station immediately after receiving an ASSIGNMENT COMPLETE message. In a normal case, the MSC would wait for a message (ANSWER) coming from

12

subscriber B, but in this case, the connection has already been switched up to subscriber B.

The signalling presented in Figure 4 then follows the normal GSM call set-up signalling between the BTS and the MSC via the permanent virtual 5 connection PVC1 and between the BTS and the BSC via the permanent virtual connection PVC2. This signalling is also irrelevant to the invention and only serves as an example of potential signalling. Therefore, rest of the messages presented in Figure 4 are not dealt with in this context but, as concerns the messages, reference is made to the above mentioned publication and the GSM specifications.

Figure 6 shows the set-up of the invention for a speech call originating from an MS. The GSM signalling in the call set-up substantially corresponds to that in Figure 4. The essential difference is that a (speech) connection is now switched in a "normal" way via an MSC, and an ATM connection is set up between a BTS and the MSC (in the example in Figure 4, the ATM connection was directly set up between the BTS and subscriber B without a through connection via the MSC).

The MSC controls an ATM switch 30 to switch a virtual connection for the call between the BTS and the MSC by sending an SNMP Set Request 20 message via a permanent virtual connection PVC4, the message containing a calling party address addr 1 (BTS) and a called party address addr 2 (MSC). The signalling between the internal elements of the ATM switch 30 then proceeds as in Figure 5. A signalling unit SIGN-CTRL then sends ATM\_UNI\_Setup messages to the BTS and the MSC. The BTS and the MSC 25 respond by an ATM\_UNI\_Connect message. The signalling unit SIGN-CTRL then commands a switching field 301 to switch a connection between the VPI/VCIs being allocated. The SIGN CTRL sends a connect ok response to an SNMP agent, the response containing the addresses addr 1 and addr\_2 and the VPI/VCI values added thereto. The SNMP agent sends an SNMP\_Get\_Response message to the MSC via the connection PVC4, the message containing said VPI/VCI values. ASSIGNMENT REQUEST and CHANNEL ACTIVATION messages then follow the above described example, the GSM signalling thereupon proceeding entirely according to the GSM.

Yet another example describes a handover between two BTSs 35 connected to the same ATM switch. Such a handover may be performed according to the same principles presented in the call set-up example. Figure 7

shows an example of a handover in the case when a BSC decides upon the moment of performing the handover (as in the GSM system). In Figure 7, solid lines illustrate GSM messages and dashed lines illustrate non-GSM messages related to the control of the ATM switch of the invention.

As known from before, an MS measures, in addition to a serving base station, downlink signals from a particular group of neighbouring base stations. The MS regularly reports on this measurement data to a BSC that makes a handover decision on the basis of the data. In Figure 7, an MS sends a measurement report to the currently serving base station BTS\_o (hereinafter referred to as an old base station) in a measurement report message. The BTS\_o forwards the measurement report to the BSC in ATM cells via a permanent virtual connection PVC2. Let us assume that the BSC decides on the basis of the measurement results sent by the MS (and according to the handover algorithm being used) that the call should be handed over from the old base station BTS\_o to a new base station BTS n.

After making the handover decision, the BSC sends an SNMP\_Set\_Request message to an ATM switch via a virtual connection PVC4. This message contains a command to switch a traffic channel as a virtual circuit between the new base station BTS n and the ATM switch. In other words, the message contains an address addr\_1 for the new base station. The SNMP agent, the MIB data base and the signalling unit SIGN-CTRL in the ATM switch communicate like in Figure 4 and the signalling unit obtains information on the ATM switch port whereto the BTS n is connected and the VPI/VCI value associated with the ATM switch port. The signalling unit SIGN-25 CTRL then sends an ATM\_UNI\_Setup message to the new base station BTS\_n. The BTS\_n accepts the call by sending an ATM\_UNI\_Connect message. The signalling unit SIGN-CTRL controls a switching field 301 to switch a logical connection between the ATM switch and the BTS to the logical connection of the other party of the call. Then, the SIGN-CTRL gives a connect\_ok response to the SNMP agent, the response containing the address addr\_1 and the corresponding VPI/VCI value. The SNMP agent sends an SNMP\_Get\_Response message to the BSC via the virtual connection PVC4, the message containing the address addr 1 and said VPI/VCI value.

After receiving the VPI/VCI values delivered in the 35 SNMP\_Get\_Response message for the virtual connection that is switched, the BSC then forwards this information in a CHANNEL ACTIVATION message

5

(via a permanent virtual connection) to the new base station BTS\_n that thus receives information on the channels to be switched for each ATM connection (VPI/VCI). This requires that the modifications described in the previous example must be made to the CHANNEL ACTIVATION message. The BTS n 5 acknowledges by sending a CHANNEL\_ACTIVATION ACK message. The BSC sends a HANDOVER\_COMMAND message to the old base station BTS o via a permanent virtual connection. This message contains information on the new base station BTS\_n. Next, a handover according to the GSM specifications is performed from the old base station to the new base station. As a result of the handover, a radio interface traffic channel reserved for the call in the BTS n is switched to the logical connection set up between the ATM switch and the new base station BTS n. The GSM signalling associated with the handover is irrelevant to the invention, and, therefore, is not described in more detail in this context. As regards a more detailed description of the 15 messages presented in Figure 7, reference is made to the above mentioned publication and the GSM specifications. The signalling between the base stations BTS and the base station controllers BSC naturally takes place through the permanent virtual connections of the invention.

After receiving information from the new base station BTS\_n about 20 the accomplishment of the handover on a radio path, the BSC commands the ATM switch to switch a call from the virtual connection of the old base station BTS 0 to the virtual connection of the new base station BTS\_n. More precisely, the BTS sends an SNMP Set Request message to the ATM switch via the connection PVC4. Since the switching from the old virtual connection to 25 the new one is performed only on the calling party side, from the BTS\_0 at the BTS n (locally), ATM signalling is not required at this moment. The virtual connection is maintained unchanged towards the other party. Thus, the ATM switch acts as an anchor point of the handover during the handover of the invention. The SNMP\_Set\_Request message sent by the BSC also contains a 30 command to release the old virtual connection to the old base station BTS\_0. This command can also be sent as a separate message. As a result of the command, the signalling unit SIGN-CTRL of the ATM switch sends an ATM UNI Release message to the old base station BTS\_0. This message indicates that the connection has been released and that the old base station 35 BTS 0 should deallocate the virtual channel and prepare to release the connection after sending an ATM\_UNI\_Release\_complete message. The BTS\_0 sends said ATM\_UNI\_Release\_complete message to the ATM switch. Then, the BTS\_o and the ATM switch release the connection. In an SNMP\_Get\_Response message, the ATM switch informs the BSC of the switching that has been performed and of the old connection that has been released. The BSC informs the MSC of the accomplishment of the handover via a connection PVC3.

Next, normal GSM signalling takes place. The BSC commands the old base station BTS\_0 to deallocate the radio channel resources by sending a RF\_CHANNEL\_RELEASE GSM message via a permanent virtual connection PVC2. The BTS\_0 acknowledges by sending a RF\_CHANNEL\_RELEASE\_ACK message. The handover is now completed.

The accompanying drawings and the description related thereto are only intended to illustrate the present invention. The details of the invention can be modified within the scope and spirit of the appended claims.

10

granger of the fire water file

#### CLAIMS:

1. A wireless ATM network comprising mobile stations, base stations and at least one ATM switch (30), the base stations (BTS) being connected to the ATM switch by a user-network-interface (UNI), character-5 ized in that

at least one controlling mobile network element (MSC, BSC) is connected to said ATM switch (30) by the UNI interface to carry out a call control and mobility management,

a first permanent ATM virtual channel is provided between said mo-10 bile network element (MSC, BSC) and each base station (BTS) for transferring call control and mobility management signalling transparently therebetween through the ATM network (3),

said mobile network element (MSC, BSC) is arranged to remotely control said ATM switch (30) to switch the ATM virtual channels dynamically between the base stations (BTS) and another point in the ATM network.

A mobile network comprising mobile stations (MS), base stations (BTS), at least one controlling PLMN network element (MSC, BSC) that is responsible for call control and mobility management, and an ATM transmission network (3) comprising at least one ATM switch (30), the base stations (BTS) and said controlling mobile network element (MSC, BSC) being connected to the ATM switch by a user-network-interface (UNI), characterized in that

a first permanent ATM virtual channel is provided between said mobile network element (MSC, BSC) and each base station (BTS) for transferring call control and mobility management signalling transparently therebetween through the ATM transmission network (3).

said mobile network element (MSC, BSC) is arranged to remotely control said ATM switch (30) to switch ATM virtual channels dynamically between the base stations (BTS) and another point in the ATM transmission network (3).

3. A network as claimed in claim 1 or 2, characterized in that

a second permanent ATM virtual channel is provided between the mobile network element (MSC, BSC) and the ATM switch (30),

the mobile network element (MSC, BSC) is arranged to remotely control the ATM switch (30) via said second permanent ATM virtual channel.

- 4. A network as claimed in claim 1, 2 or 3, **characterized** in that the remote control protocol between the mobile network element (MSC, BSC) and the ATM switch (30) is a Simple Network Management Protocol (SNMP).
  - 5. A network as claimed in claim 1, c h a racterized in that the remote control between the mobile network element (MSC, BSC) and the ATM switch (30) is based on UNI signalling.
- 6. A network as claimed in claim 1, characterized in that said at least one mobile network element comprises a mobile telephone exchange (MSC) and/or a base station controller (BSC).
- 7. A network as claimed in any one of the preceding claims, characterized in that the ATM switch comprises means (SNMP AGENT, MIB, SIGN.CTRL, 301) that perform a standard UNI signalling procedure between the ATM switch, the base station and said another point as a response to the remote control of the mobile network element, the UNI procedure setting up, releasing or reswitching a logical virtual channel for a call.
- 8. A network as claimed in claim 1, c h a r a c t e r i z e d in that the ATM switch (30) is able to switch the call directly to the other party without 20 having to switch the call via said mobile network element.
  - 9. A method for mobility management and call control in a wireless ATM network comprising mobile stations, base stations and at least one ATM switch, the base stations being connected to the ATM switch by a user-network-interface (UNI), characterized by
  - transferring signalling related to the mobility management and the call control transparently between the base stations and said mobile network element through the ATM network on permanent logical virtual channels,
    - setting up, in the ATM switch, call-specific logical virtual channels between the base stations and other parties by using UNI signalling,
      - remote controlling the ATM switch from said mobile network unit.
- 10. A method for mobility management and call control in a mobile network comprising mobile stations, base stations, at least one controlling mobile network element that is responsible for call control and mobility management, and an ATM transmission network comprising at least one ATM switch, the base stations and said controlling mobile network element being

。 医乳腺性溶液 A. M. Sellar 1980年 1980年 2011年 1972年 1973年 1

25

15

connected to the ATM switch by a user-network-interface (UNI), characterized by

performing operations related to the call control and the mobility management in a separate controlling mobile network element, the mobile network element being connected to said ATM switch by a UNI interface,

transferring signalling related to the mobility management and the call control transparently between the base stations and said mobile network element through an ATM network on permanent logical virtual channels,

setting up, in the ATM switch, call-specific logical virtual channels between the base stations and other parties by using UNI signalling,

remotely controlling the ATM switch from said mobile network unit.

- 11. A method as claimed in claim 9 or 10, characterized by remotely controlling the ATM switch via said permanent ATM virtual channel between the mobile network element and the ATM switch.
- 12. A method as claimed in claim 11, characterized in that the remote control protocol between the network element and the ATM switch is based on a Simple Network Management Protocol (SNMP) or UNI signalling.
- 13. An ATM switch element for a wireless ATM network or an ATM transmission network of a mobile network, which ATM switch element can be connected by a UNI interface to base stations (BTS) and to at least one controlling mobile network element (MSC, BTS) responsible for call control and mobility management, characterized in that

the ATM switch (30) is provided with remote control by means of which the mobile network element (MSC, BSC) is able to control the ATM switch (30) to switch ATM virtual channels dynamically between the base stations (BTS) and another point in the ATM network.

- 14. An ATM switch element as claimed in claim 13, characterized in that said remote control is implemented via a permanent ATM virtual channel between the mobile network element (MSC, BSC) and the ATM switch (30).
- 15. An ATM switch element as claimed in claim 13 or 14, char-acterized in that the remote control protocol between the mobile network element (MSC, BSC) and the ATM switch (30) is a Simple Network 35 Management Protocol (SNMP).

- 16. An ATM switch element as claimed in claim 13, 14 or 15, characterized in that the remote control between the mobile network element (MSC, BSC) and the ATM switch (30) is based on UNI signalling.
- 17. An ATM switch element as claimed in any one of claims 13 to 16, **characterized** in that the ATM switch comprises means (SNMP, AGENT, MIB, SIGN.CTRL, 301) that perform a standard UNI signalling procedure between the ATM switch, the base station and said another point as a response to the remote control of the mobile network element, the procedure setting up, releasing or reswitching a logical virtual channel for a call.
- 18. An ATM switch element as claimed in any one of claims 13 to 17, characterized in that the ATM switch (30) is able to switch a call directly to the other party without having to switch the call via said mobile network element.
- 19. A mobile network element to be connected to base stations 15 (BTS) by a UNI interface via a wireless ATM network or via an ATM transmission network, characterized in that

said mobile network element (MSC, BSC) is responsible for call control and mobility management in the network and is arranged to perform call control and mobility management signalling with each base station (BTS) transparently through the ATM transmission network (3) via permanent ATM virtual channels between the mobile network element and the base stations (BTS),


2 2 K


said mobile network element (MSC, BSC) is arranged to remotely control an ATM switch (30) in the wireless ATM network or in the ATM transmission network to switch ATM virtual channels dynamically between the base stations (BTS) and another point in the ATM network.


- 20. An ATM switch element as claimed in claim 19, characterized in that said remote control is implemented via the permanent ATM virtual channel between the mobile network element (MSC, BSC) and the ATM switch (30).
  - 21. A mobile network element as claimed in claim 19, characterized in that the remote control protocol between the mobile network element (MSC, BSC) and the ATM switch (30) is a Simple Network Management Protocol (SNMP).


10


- 22. A mobile network element as claimed in claim 19, 20 or 21, characterized in that the remote control between the mobile network element (MSC, BSC) and the ATM switch (30) is based on UNI signalling.
- 23. A mobile network element as claimed in claim 19, 20, 21 or 22, 5 characterized in that the mobile network element is a mobile telephone exchange (MSC) or a base station controller (BSC).













9836612A2 1 >





(orden) Mold abod sint

## PCT

# WORLD INTELLECTUAL PROPERTY ORGANIZATION International Bureau



#### INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 6:

**A3** 

(11) International Publication Number:

WO 98/36612

H04Q 7/24

(43) International Publication Date:

20 August 1998 (20.08.98)

(21) International Application Number:

PCT/FI98/00125

(22) International Filing Date:

11 February 1998 (11.02.98)

(30) Priority Data:

970602

12 February 1997 (12.02.97) FI

(71) Applicant (for all designated States except US): NOKIA TELECOMMUNICATIONS OY [FI/FI]; Keilalahdentie 4, FIN-02150 Espoo (FI).

(72) Inventors; and

- (75) Inventors/Applicants (for US only): VIALÉN, Jukka [FI/FI]; Tyrskykuja 3 B 13, FIN-02320 Espoo (FI). MÄENPÄÄ, Sanna [FI/FI]; Hauenkalliontie 8 D 9, FIN-02170 Espoo
- (74) Agent: KOLSTER OY AB; Iso Roobertinkatu 23, P.O. Box 148, FIN-00121 Helsinki (FI).

(81) Designated States: AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CU, CZ, DE, DK, EE, ES, Fl, GB, GE, GH, GM, GW, HU, ID, IL, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, UA, UG, US, UZ, VN, YU, ZW, ARIPO patent (GH, GM, KE, LS, MW, SD, SZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European patent (AT, BE, CH, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, ML, MR, NE, SN, TD, TG).


#### Published

With international search report.

Before the expiration of the time limit for amending the claims and to be republished in the event of the receipt of amendments. In English translation (filed in Finnish).

(88) Date of publication of the international search report: 15 October 1998 (15.10.98)

(54) Title: MOBILITY AND CALL CONTROL IN AN ATM ENVIRONMENT



#### (57) Abstract

The invention relates to ATM (Asynchronous Transfer Mode) systems, and particularly to mobility and call control management therein. A wireless ATM network comprises at least one ATM switch (30), and base stations (BTS) connected to the ATM switch by a user-network-interface (UNI) interface. In addition, at least one controlling network element of a conventional PLMN network, such as a mobile telephone exchange (MSC) or a base station controller (BSC), which is responsible for the mobility management and call control, is connected to the ATM network by the UNI interface. A permanent virtual channel is provided between the base station and the controlling PLM element for PLM-specific signalling (signalling related to, for example, call control, mobility management or radio resource management). The ATM switch (30) therebetween forwards the signalling without interpreting it in any way. The PLMN element (MSC, BSC) remotely controls the ATM switch to switch a virtual connection between the base station (BTS) and another point according to the ATM standards.

## FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
ΑT	Austria	FR	France	LU	Luxembourg	SN	Senegai
ΑU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
ΑZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN '	Guinea	MK	The former Yugoslav	TM	Turkmenistan
BF	Burkina Faso	GR	Greece		Republic of Macedonia	TR	Turkey
BG	Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MN	Mongolia	UA	Ukraine
BR	Brazil	IL	Israel	MR	Mauritania	UG	Uganda
BY	Belarus	18	Iceland	MW	Malawi	US	United States of America
CA	Canada	IT	' Italy	MX	' Mexico	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NE	Niger	VN	Viet Nam
CG	Congo	KE	Kenya	NL '	Netherlands	ΥU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NO	Norway	zw	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's	NZ	New Zealand		
CM	Cameroon		Republic of Korea	PL	Poland	•	
CN	China	KR	Republic of Korea	PT	Portugal		
CU	Cuba	KZ	Kazakstan	RO	Romania		
CZ	Czech Republic	LC	Saint Lucia	RU	Russian Federation	-	
DE	Germany	LI	Liechtenstein	SD	Sudan		
DK	Denmark	LK	Sri Lanka	SE	Sweden	11 11 11	
EE	Estonia	LR	Liberia	SG	Singapore		

# INTERNATIONAL SEARCH REPORT

International application No.

PCT/FI 98/00125

A. CLAS	SIFICATION OF SUBJECT MATTER		
IPC6: I	H04Q 7/24 o International Patent Classification (IPC) or to both na	ational classification and IPC	
	OS SEARCHED		
	ocumentation searched (classification system followed by	y classification symbols)	
IPC6: I	<del></del>		
Documentat	tion searched other than minimum documentation to the	e extent that such documents are included in	the fields scarched
	FI,NO classes as above		
Electronic d	ata base consulted during the international search (name	e of data base and, where practicable, search	terms used)
C. DOCU	MENTS CONSIDERED TO BE RELEVANT		
Category*	Citation of document, with indication, where app	propriate, of the relevant passages	Relevant to claim No.
Y	EP 0679042 A2 (ROKE MANOR RESEAF 25 October 1995 (25.10.95), line 16 - column 5, line 11; line 38 - line 43; column 6, column 7, line 55 - column 8	column 3, ; column 5, , line 35 - line 38,	1-23
	<del></del>		
Y	EP 0534716 A2 (NEC CORPORATION), (31.03.93), column 2, line 1	, 31 March 1993 l1 - column 4, line 54	1-23
	<b></b>		
P,A	EP 0796022 A2 (MOTOROLA, INC.), (12.03.97), abstract	12 March 1997	1-23
	10 m 10 m 22 m	1	
		• • • • • • • •	
		. 1	
X Furth	er documents are listed in the continuation of Box	C. See patent family annex	
"A" docume	categories of cited documents:  nt defining the general state of the art which is not considered particular relevance	"T" later document published after the inte date and not in conflict with the applic the principle or theory underlying the	cation but cited to understand
"E" criier do	not published on or after the international filing date nt which may throw doubts on priority claim(s) or which is establish the publication date of another citation or other	"X" document of particular relevance: the considered novel or cannot be considered when the document is taken alone	claimed invention cannot be red to involve an inventive
special i	reason (as specified)  nt referring to an oral disclosure, use, exhibition or other	"Y" document of particular relevance; the considered to involve an inventive step combined with one or more other such	when the document is
	nt published prior to the international filing date but later than rity date claimed	being obvious to a person skilled in the "&" document member of the same patent	e art
Date of the	actual completion of the international search	Date of mailing of the international s	
	ıst 1998	01- 09- 1998	·
Name and	mailing address of the ISA/	Authorized officer	
Box 5055,	Patent Office S-102 42 STOCKHOLM No. +46 8 666 02 86	Göran Petersson Telephone No. + 46 8 782 25 00	
	A (210 (sepand -b) (but (1002)	Telephone No. + 46 8 782 25 00	

Form PCT/ISA/210 (second sheet) (July 1992)

# INTERNATIONAL SEARCH REPORT

International application No.

DC1	T	98	/n	<b>N</b> 1	25
 	 _	30	, ,	υı	

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No
A	GB 2268360 A (ROKE MANOR RESEARCH LIMITED), 5 January 1994 (05.01.94), page 3, line 16 - page 5, line 16	1-23
A	GB 2268359 A (ROKE MANOR RESEARCH LIMITED), 5 January 1994 (05.01.94), page 6 - page 7, abstract	1-23
P,A	WO 9728664 A1 (NOKIA TELECOMMUNICATIONS OY), 7 August 1997 (07.08.97), page 10, line 23 - line 36, abstract, see the figures	1-23
A	US 5519689 A (YOUNG-II KIM), 21 May 1996 (21.05.96), abstract 	1-23
	·	

Form PCT/ISA/210 (continuation of second sheet) (July 1992)

# INTERNATIONAL SEARCH REPORT

Information on patent family members

27/07/98

International application No. PCT/FI 98/00125

	atent document I in search repo	rt	Publication date		Patent family member(s)		Publication date
EP	0679042	A2	25/10/95	FI GB GB	951920 2288950 9408122	A,B	24/10/95 01/11/95 00/00/00
EP	0534716	A2	31/03/93	JP US	5091035 5619551		09/04/93 08/04/97
EP	0796022	A2	12/03/97	NON	E		
GB	2268360	A	05/01/94	EP EP FI FI GB	0577959 0577960 932899 932900 2268359	A A A	12/01/94 12/01/94 25/12/93 25/12/93 05/01/94
:-	·			JP JP NO NO US	6077989 6098370 932303 932304 5359603	A A A	18/03/94 08/04/94 27/12/93 27/12/93 25/10/94
GB	2268359	A	05/01/94	EP EP FI FI GB JP JP NO NO US	0577959 0577960 932899 932900 2268360 6077989 6098370 932303 932304 5359603	A A A A,B A A	12/01/94 12/01/94 25/12/93 25/12/93 05/01/94 18/03/94 08/04/94 27/12/93 27/12/93 25/10/94
WO	9728664	A1	07/08/97	AU DE FI	1548097 29710804 960404	U	22/08/97 04/12/97 30/07/97
us Us	5519689	Α	21/05/96	JP	7170270	A	04/07/95

Form PCT/ISA/210 (patent family annex) (July-1992)

Soog Blank Instig